

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-095-19041-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1963
07-09-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Smith of Kent Well Servicing Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Ks.

Lease Name: Berkenbaugh "B" Well No. # 3

Location: NW SE NE Sec. 33 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4270 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

240' of 8 5/8" surface pipe, cement circulated with 145
sacks. 4269' of 5 1/2" long string, cemented with 100 sacks.
Top perforation 4193'. Sand to 4180', cement with 5 sacks.
Fill hole with mud to 240', 10' rock bridge, cement with
20 sacks. Fill hole with mud to 40', 10' rock bridge, cement
with 10 sacks to base cellar.

Very truly yours,

Archie Elving
Conservation Division Agent