

State of Kansas



15-093-10005-0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Hicks of E.E.Fogelson Et.Al. has this

date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: E.E.Fogelson Et.Al.

Complete Address: 2010 Republic Bank Building, Dallas, Texas

Lease Name: H.E.Johnston Well No. # 1

Location: C NE/4 SW/4 Sec. 17 Twp. 26S Rge. 38 (E)(W)

County Kearney Total Depth 5600' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hicks was instructed to plug the well as follows:

8 5/8" --1950' Circulated w/cement.

Mud 5600' to 2600' 70 Sax.cement 2600' to 2300'

Mud 2300' to 700' 35 Sax.cement 700' to 600'

Mud 600' to 40' 15 Sax.cement 40' to surface.

Very truly yours,

F. Hugh Scott
Conservation Division Agent