



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 16, 1975

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-20315-0000

11-24-75

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ross Crawford of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Crawford guarantees payment of the plugging fee.

Operator's full Name: Gear Petroleum Company

Complete Address: 1325 Vickers-KSB&T Bldg., Wichita, Kansas

Lease Name: Davis Well No. 1

Location: C NE SW Sec. 2 Twp. 23 Rge. 9 (E)(W) X

County: Reno Total Depth 2743' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crawford was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe at 450'. Pump 25 sacks cement through drill pipe at 215'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent