

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-20108-0600

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orr of Kathol Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Kathol Petroleum Inc.

Complete Address: 900 Sutton Place. Wichita, Kansas

Lease Name: Groth Well No. # 1

Location: NW NW NE Sec. 11 Twp. 23S Rge. 9 (E)(W)

County: Reno Total Depth 3670' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Orr was instructed to plug the well as follows:

8 5/8"-238'-Circulated w/cement.

Mud 3670' to 500'. Spotted 25 Sax.cement 500' to 425'.

Mud 425' to 225'. Spotted 25 Sax.cement 225' to 150'.

Mud 150' to 40'. Spotted 10 Sax.cement 40' to 0.

Sun Cementing Company.

Very truly yours,


Conservation Division Agent