

15.007.30396.00.04

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1967

CONSERVATION DIVISION

Operator's Full Name Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg., Wichita, Kansas

Lease Name Shutts "A" Well No. # 1

Location C NW SW NE Sec. 35 Twp. 30 Rge. 15 (E) (W) W

County Barber Total Depth 4651'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down.

Plugging Contractor: Walters Drilling Company

Address: 400 Insurance Bldg., Wichita, Kansas License No.

Operation Completed: Hour 12:30PM Day 7th Month Jan. Year 1967

The Above well was plugged as follows:

794' of 10 3/4" surface pipe, cement circulated. Hole was filled with
drilling mud to 400', 1st cementing plug, bridged with 2 sacks of dry
cement and 1/2 sack of hulls on fluid at 400', and cemented with 23 sacks.
hole was filled with drilling mud to 40', 2nd cementing plug, bridged
with 1 sack of ^{CEMENT} hulls, and 1 sack of hulls on fluid at 40', and cemented
with 9 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/10/67
INV. NO. 4580-u

Signed: Archie Elving
Well Plugging Supervisor