

15.063.00209.00.00

KANSAS
STATE CORPORATION COMMISSION

R

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Gove

Location: C NE SE Sec. 31 Twp. 14 Rge. 29 (E) (W)

Name of Field: _____ Total Depth: 4359

I have this date completed supervision of plugging of:

Lease Name: Lundgren Well No. #3

Operator's Full Name: Wycoff Bros.

Complete Address: Russell Springs, Kans

Plugging Contractor: Barnes & Sons Pipe Pulling

Address: Russell, Kans. License No. 9

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 6pm Day 4 Month Oct. Year 1958

The above well was plugged as follows:

TD-4359 8 5/8" set at 150' 4 1/2" set at 4355 PB to 3960 Perf. 3922

Sand to 3910' with 4 sax cement, shot pipe at 3100' and pulled same out of hole. Used pump truck to spueeze hole with mud, then set 20 sax cement at 600' mud to 240' and set another 20 sax cement, mud to 40' built solid rock bridge, and ten sax cement to bottom of cellar.

Gilbert P. Leiker

Signed: Gilbert P. Leiker
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 31 T 14 R 29 W
BOOK PAGE 136 LINE 5

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1958
CONSERVATION DIVISION
Wichita, Kansas