

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

APR 2 - 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Marvin Lawton

Complete Address P.O. Box 357, Wichita, Kansas 67201

Lease Name Clark Miller "B" Well No. 1

Location C NE NE Sec. 7 Twp. 24 Rge. 4 (E) (W) X

County Reno Total Depth 3414'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Dunbar Drilling Company

Address 5252 N. Broadway, Wichita, Kansas License No. 709

Operation Completed: Hour 1:30 PM Day 1 Month April Year 1974

The above well was plugged as follows:

7" plug pushed to 2860'. Hole filled with sand to 2850' and hole cemented with 6
sacks cement. Hole filled with mud to 215'. Rock bridge set from 215' to 200' and
hole cemented to base of cellar with 4 yards ready-mix concrete.

I hereby certify that the above well was plugged as herein stated.

Signed: *William J. Loman*
Well Plugging Supervisor

INVOICED

DATE 4/3/74

ENV. NO. 8875-W