

RR

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kansas-Nebraska Natural Gas Co., Inc.

Complete Address: 300N. St. Joseph Ave., Hastings, Nebraska 68901

Lease Name Eichorn Well No. 1

Location C W/2~~X~~ ~~XA~~ Sec. 18 Twp. 24 Rge. 31 (E) (W)

County Finney Total Depth 2687'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 28 Month 12 Year 1968

The Above well was plugged as follows:

8 5/8" to 372' circulated w/ cement. 5 1/2" to 2683' cemented.

Top perforations 2632' Plug bottom w/ 25 sacks cement.

Top of cement 2414' Mud 2414' to 400'

Spotted 50 sacks cement 400' to 250' Mud 250' to 40'

Plug. Halls & 10 sacks cement 40' to 0'. Company Pump

Pulled 1423' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 12-30-68

INV. NO. 9111-W