


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County. Sec. 31 Twp. 20 Rge. 11 (E) (W)
Location as "NE/CNW¹/₄SW¹/₄" or footage from lines C S/2 N/2 NE/4
Lease Owner Henderson Oil Company
Lease Name Johnson Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed..... 19.....
Application for plugging filed..... 19.....
Application for plugging approved..... 19.....
Plugging commenced 3-15-51..... 19.....
Plugging completed 3-18-51..... 19.....
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Stough
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	312'	000'
				5-1/2"	3373'	2749'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Rocked hole from 3373' to 3360' and ran 5 sacks cement. Mudded hole to 310', set 10' rock bridge, and ran 15 sacks cement at 300'. Mudded hole to 18' and ran 5 sacks cement. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1951
CONSERVATION DIVISION
Wichita, Kansas
3-27-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Henry Kollman
Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

J. A. HENDERSON, employee of owner (employee of owner) or (owner operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Henderson
502 Orpheum Bldg. Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 51

Joe Swanson
Notary Public.

My commission expires April 28, 1954

PLUGGING
FILE SEC 31 T 20 R 11 W
BOOK PAGE 17 LINE 40

15-009-0585300 @

WELL LOG

The Henderson Oil Company et al - owners - D. C. Johnson #2
C S/2 N/2 NE/4
Section 31-20-11W
Barton County, Kansas

Elevation 1814 R.B.

Tops at Rotary Bushing

Figures indicate bottom of formation

Topeka 2711
Heebner 2989
Base Oread 3020
Brown Lime 3121
Lansing 3136
Simpson 3366
Arbuckle 3373

0 - 60 Sand
160 Sand and Gravel
215 Shale and Sand
260 Shale and Red Bed
570 Shale, shells, Red Bed
590 Anhydrite
1075 Shale and shells
1260 Shale and Salt
1435 Shale and Lime
2290 Lime and Shale
2700 Shale and Lime
2780 Lime
3150 Lime and Shale
3366 Lime
3373 Shale
3375 Lime
3375 Rotary T. D.

Pipe Record:

8 5/8" set at 312'
5 1/2" set at 3373'

Rotary commenced Sept. 13, 1950
Rotary completed Sept. 21, 1950

Cable Tools commenced Sept. 25, 1950
Cable Tools completed Oct. 13, 1950

CABLE TOOL WORK:

3375-77 Lime
7 Kone Shot 3376 - 73
Acid - 1000 gal.
Acid - 1000 gal.
3377-82 Lime
Acid - 2000 gal.
3382-90 Lime
3390-97 Lime and Shale
3397-3420 Shale
Plug back to 3384
1000 gal Jell Acid
Swab 40 gal fluid / hr 20% oil

RECEIVED
CONSERVATION COMMISSION
MAR 27 1951
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, J. A. Henderson, Secretary of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

PLUGGING
FILE SEC 31 T 20 R 11W
BOOK PAGE 67 LINE 40

J. A. Henderson

Sworn and subscribed to before me this 17th day of October, 1950.

Ina Swanson
NOTARY PUBLIC

My commission expires April 28th, 1954.