


OR 15.007.01549.00.00
Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

NORTH



Locate well correctly on above Section Flat

Barber County, Sec. 27 Twp. 30 Rge. (E) 15 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C. NE. N. E.
Lease Owner Pryor & Lockhart, Inc.
Lease Name Massey Well No. 3
Office Address 820 Union Natl Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1/29 1944
Application for plugging filed 1/29 1944
Application for plugging approved 1/29 1944
Plugging commenced 1/30 1944
Plugging completed 1/30 1944
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation Depth to top Bottom Total Depth of Well 4442 Feet

Show depth and thickness of all water, oil and gas formations,
OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10	902Ft.	None
				5 1/2	4440Ft.	3800Ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged Back 4442 to 4425 The Hole filled with cement from 4425 to 4364 and mud and bridge to 300 Ft. and cement to 280ft. and mud and bridge to 20ft. and Cement to 5ft.

Pd.
2/23/44
Na

PLUGGING
FILE SEC. 27 30 15W
BOOK PAGE 106 LINE 26

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Pryor & Lockhart Inc.
Address 820 Union Natl Bank Bldg. Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick ss.
T.P. Hendrick (employee of owner) of Pryor & Lockhart Inc.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) T.P. Hendrick
820 Union Natl Bank Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of February 1944

My commission expires Feb. 20, 1945

Notary Public.
FEB 23 1944
2-23-44

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15.007.01549.00.00

Company - PRYOR & LOCKHART, INC.
Farm - Massey No. 3.

SEC. 27 T. 30 R. 15 W
CNE NE

Total Depth. 4442' DF
Comm. 12-12-43 Comp. 1-15-44
Shot or Treated.
Contractor.
Issued. 2-26-44

County. Barber
KANSAS



CASING:
10" 902'
5 1/2" 4440' (P 3800')

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & red rock	230
shale	250
red rock	450
shale & shells	677
anhydrite	690
shale & shells	870
shale	900
shale & shells	1275
lime brkn & shale	1435
lime brkn	1450
shale & salt	1600
shale & shells	1805
shale & lime	1915
lime	1975
lime & shale brks	2025
lime	2030
lime & shale	2090
lime	2125
lime brkn & shale	2195
lime	2270
shale & lime	2330
lime & chert	2380
lime	2425
lime & shale bks	2480
lime	2515
lime & shale	2590
shale bkn lime	2645
lime & shale	3320
lime	3655
shale & lime	3680
lime	3760
shale & lime	3805
shale & shells	3843
sand & shale	3860
lime & shale	3900
lime	4070
shale & lime	4087
lime	4117
lime brkn & chert	4123
lime	4335
lime sft	4344
lime	4367
shale & lime	4436
shale	4442
Total Depth.	Derr. Flr.

PLUGGING
FILE SEC 27 T 30 R 15 W
BOOK PAGE 206 LINE 26

