

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15.063. 205 80.00.00
 WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Gove SEC. 14 TWP. 14s RGE. 29w E/W
 Location as in quarters or footage from lines:
 SW SW NE

Lease Owner Donald C. Slawson
 Lease Name Coberly AO #1 Well No. _____
 Office Address 200 Douglas Bldg., Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 1/18/83
 Plugging completed 1/24/83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom T.D. 4500'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	412'	none
				4 1/2"	4499'	3204'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged bottom with sand to 4175' & ran 4 sacks cement. Shot at 3605', 3415', & 3205'. Pulled total of 80 joints. Squeezed hole with 2 sacks hulls, 30 gel, 100 sacks cement, and 10 sacks gel. Released plug & displaced with 70 sacks cement.

Plugging complete

JAN 31 1983

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 1983

My Commission expires _____


Irene Hoover
 Notary Public.