


15.063.30106.00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Gove County, Sec. 21 Twp. 15S Rge. (E) 27W (W)

Location as "NE/CNW&SW" or footage from lines C. NE SW
Lease Owner Pickrell Drilling Company
Lease Name Owens "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 8, 1967
Application for plugging filed June 8, 1967
Application for plugging approved June 8, 1967
Plugging commenced June 8, 1967
Plugging completed June 8, 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4390' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	225'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 540'. Set plug. Cemented with 20 sacks
cement. Heavy mud to 240'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug. Cemented
with 10 sacks cement to bottom of cellar. Plugged rat
hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (owner or operator) of the above-described


well, do hereby swear on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. SEBITS
705 4th Nat'l Bank Bldg., Wichita, Ks. 67202
(Address)

Sworn to before me this 14th day of June, 1967

L. M. Whiting
L. M. Whiting Notary Public.

My commission expires May 10, 1970



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 5/29/67

Rotary Drilling Completed 6/8/67

LOCATION: Owens "A" No. 1
C NE SW Section 21-15S-27W
Gove County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (11 jts.) 8 5/8" surface casing set at 223' and cemented with 155 sacks cement. Circulated. Completed 3:30 PM, June 8, 1967. No oil string was run. D. & A., June 8, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Sand	C. F. S.
1200	Shale & Shells	3489'
1350	Red Beds	3700'
1375	Blaine	3720'
1430	Shale & Shells	3750'
1690	Sand	3780'
1906	Shale & Shells	3796'
1945	Anhydrite	3811'
2125	Shale & Shells	3830'
4250	Lime & Shale	3885'
4325	Lime, Shale & Chert	3945'
4345	Lime, Shale & Sand	3960'
4390	Lime, Shale & Chert, RTD	3980'
		4005'
		4217'
		4230'
		4290'
		4312'
		4325'
		4340'
		4350'
		4390'
		Slope Test
		2500
		3000
		4000
		S. L. M.
		3700'

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1967

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 14th day of June, 19 67, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires May 10, 1970

L. M. Whiting
L. M. Whiting Notary Public