


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15.063.00099.00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Gove County. Sec. 33 Twp. 15S Rge. 26 XXXXX (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Empire Drilling Company
Lease Name Babcock Well No. 2
Office Address 650 4th Natl. Bank Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 17 19 63
Application for plugging filed May 17 19 63
Application for plugging approved May 17 19 63
Plugging commenced May 17 19 63
Plugging completed May 17 19 63
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface-Shale		0	134	8 5/8"	110'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug set at 540' with 20 sacks cement.

Plug set at 150' with 20 sacks cement.

Plug set at 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 4th Natl. Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 63

My commission expires October 21, 1966

Lucille H. Harr
Lucille H. Harr Notary Public.

L O G

15.063.00099.00.00

COMPANY: Empire Drilling Company

CONTRACTOR: Empire Drilling Company

FARM: Babcock #2

LOCATION: C NE SW Section 33-15S-26W, Gove County, Kansas

COMMENCED: May 2, 1963 ELEVATION: 2516 KB

COMPLETED: May 17, 1963 POTENTIAL: D & A

0	to	134	Surface-Shale
134	to	3300	Shale
300	to	905	Shale-Sand-Pyrite
905	to	1200	Shale
1200	to	1374	Shale, Gyp, Base Blaine
1374	to	1530	Shale & Sand
1530	to	1935	Shale
1935	to	1974	Anhydrite
1974	to	2310	Shale
2310	to	2420	Salt
2420	to	2435	Shale
2435	to	2620	Shale & Shells
2620	to	2870	Lime & Shale
2870	to	2930	Lime
2930	to	3020	Limy Dolomite with shale streaks
3020	to	3195	Lime & Shale
3195	to	3255	Lime & Shale with Sand streaks
3255	to	3810	Lime and Shale
3810	to	3865	Lime-Shale & Chert
3865	to	3971	Lime & Shale
3971	to	4063	Lime
4063	to	4085	Lime & Chert
4085	to	4110	Lime
4110	to	4340	Lime & Shale
4340	to	4385	Lime
4385	to	4415	Lime & Shale - Chert
4415	to	4430	Lime with Chert
4430			Log Total Depth

SET: 110' of 8 5/8" with 75 sacks cement.

SCHLUMBERGER ELECTRIC LOG TOPS:

Waubensee	3361	-845
Topeka	3551	-1035
Queen Hill	3634	-1118
Heebner	3767	-1251
Toronto	3788	-1272
Lansing	3807	-1291
Base Kansas City	4108	-1592
Pawnee	4216	-1700
Fort Scott	4257	-1741
Cherokee Group	4309	-1793
Cherokee Limestone	4317	-1801
Conglomerate	4393	-1877
Mississippi	4414	-1898
Log Total Depth	4430	

C E R T I F I C A T I O N

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Babcock #2, C NE SW Section 33-15S-26W, Gove County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 20th day of May, 1963.

My commission October 21, 1966.

Lucille H. Harr
Lucille H. Harr, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1963
CONSERVATION DIVISION
Wichita, Kansas