


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Reno County, Sec. 9 Twp. 23S Rge. 10W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner O. A. Sutton
Lease Name Weber Well No. 1
Office Address 407 Ins. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 23 19 59
Application for plugging filed July 20 19 60
Application for plugging approved July 20 19 60
Plugging commenced July 20 19 60
Plugging completed July 26 19 60
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hempel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3767' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	259'	
				5-1/2"	3766'	1941.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand 3767'-3587'.
Dumped 5 sacks cement at 3587'.
Mud to 240'. Put in 10' rock bridge with 3 sacks cement on top. Mud to 35'. 10' rock bridge with 10 sacks cement on top.

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1960 8-4-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wilson, Inc., Stafford, Kansas
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. G. Comstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. G. Comstock
D. G. Comstock
407 Ins. Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of August, 1960

My commission expires Feb. 5, 1964
Sara Wimberly Notary Public.



O. A. Sutton, Weber #1
SE SE NE Sec. 9-23S-10W
Reno County, Kansas

15-155-00273-0000

Commenced - July 10, 1959
Completed - July 23, 1959
Casing - 259' of 8-5/8" csg. w/225 sax HA5
3766' of 5-1/2" w/225 sax Pozmix
Elevation - 1768 KB

DRILLERS LOG

0 - 259	Surface soil, sand and shale
259 - 700	Red bed
700 - 1040	Shale and shells
1040 - 1495	Shale and shells
1495 - 1540	Shale and shells
1540 - 1613	Lime and shells
1613 - 1840	Lime
1840 - 2030	Lime
2030 - 2150	Lime
2150 - 2400	Lime and shale
2400 - 2524	Lime
2524 - 2735	Lime and shale
2735 - 2825	Lime and shale
2825 - 2884	Lime
2884 - 2995	Lime
2995 - 3045	Lime
3045 - 3160	Lime and shale
3160 - 3219	Lime and shale
3219 - 3276	Lime
3276 - 3296	Lime
3296 - 3360	Lime
3360 - 3393	Lime
3393 - 3484	Lime
3484 - 3527	Lime
3527 - 3606	Lime and shale
3606 - 3620	Viola
3620 - 3661	Viola
3661 - 3677	Viola
3677 - 3680	Simpson
3680 - 3714	Simpson
3714 - 3743	Simpson
3743 - 3767	Arbuckle
3767 -	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1960
CONSERVATION DIVISION
Topeka, Kansas

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON & SONS DRILLING CO.

By Henry D. Ficken

Subscribed and sworn to before me this 28th day of July, 1959.

Lorraine Shellout
Notary Public

My commission expires June 1, 1960.