

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market #1000 Wichita, KS 67202

PHONE# (316)267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed         

Character of Well Oil

Plugging Commenced 9-11-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-13-96

The plugging proposal was approved on          (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3360'

Show depth and thickness of all water, oil and gas formations.

9-22-96

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	433'	none.
				5 1/2	3357'	1020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from          feet to          feet each side. Plugged off bottom with sand to 3296' & 5 sks cement. Checked hole, pipe was loose at 1020'. Pulled casing to 716', spotted 35 sks cement. Pulled casing to 480', circulated cement to surface w/150 sks. Pulled rest of casing, topped off with 10 sks. 60/40 4%. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 96

[Handwritten Signature]  
Notary Public

My Commission Expires:         

