


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kingman County, Sec. 15 Twp. 29 Rge. 6 (X) (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Stelbar Oil Corporation, Inc.
Lease Name Ravenstein Well No. 1
Office Address 310 Petroleum Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 11, 1963
Application for plugging filed June 11, 1963
Application for plugging approved June 11, 1963
Plugging commenced June 11, 1963
Plugging completed June 11, 1963
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4610 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	224	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plugged hole with mud to 240 feet. Set plug, ran 1/2 sack hulls and 20 sacks cement. Plugged hole with mud to 40 feet, ran 1/2 sack hulls, set plug and ran 8 sacks cement. Ran 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stelbar Oil Corporation, Inc.
Address 310 Petroleum Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Bertrand M. Lester, Jr. (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester Jr.
310 Petroleum Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of June, 1963

My commission expires May 7, 1966.

Talia Zuhars
Talia Zuhars Notary Public.



LOG

Farm: Ravenstein
 Well No. 1
 C SE NE Sec. 15-29S-6W
 Kingman County, Kansas

Owner: Stelbar Oil Corporation, Inc.
 Contractor: Stelbar Oil Corporation, Inc.
 Drilling Commenced: 5-25-63
 Drilling Completed: 6-11-63

Elevation: 1536 RB
 1533 DF
 1531 GL

8-5/8" Casing set at 224' w/ 200 Sacks Reg

	From	To
Sand & Clay	0	30
Shale & Shells	30	1020
Shale & Lime	1020	1285
Lime	1285	1585
Lime & Shale	1585	2540
Shale & Lime	2540	2975
Shale & Lime - Sdy.	2975	3101
Shale & Lime	3101	3254
Lansing	3254	3280
Lansing Lime	3280	3330
Lime	3330	3423
Shale & Lime	3423	3504
Kansas City Lime	3504	3774
Shale & Lime	3774	3816
Lime & Shale	3816	4069
Miss. Chert	4069	4195
Miss. Lime	4195	4339
Shale & Lime	4339	4426
Misener (Sand)	4426	4433
Shale	4433	4446
Viola Lime	4446	4463
Simpson Dolo	4463	4549
Shale & Lime	4549	4579
Arbuckle	4579	4610
Rotary Total Depth	4610	

RECEIVED
 STATE CORPORATION COMMISSION

JUN 21 1963

CONSERVATION DIVISION
 Wichita, Kansas

Plugged hole with mud to 240 feet. Set plug, ran 1/2 sack hulls and 20 sacks cement.
 Plugged hole with mud to 40 feet, ran 1/2 sack hulls, set plug and ran 8 sacks cement.
 Ran 2 sacks cement in rat hole.