

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15095-20457-0000

LEASE NAME Albrecht

WELL NUMBER # 1

SPOT LOCATION NE NE SE

SEC. 18 TWP. 29 SRGE. 6W (A) or (W)

COUNTY Kingman

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Robert Campbell Oil & Gas Operations

ADDRESS 260 N. Rock Rd. Suite 110, Wichita, Ks. 67206

PHONE # (316) 685-6001 OPERATORS LICENSE NO. 5348

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

RECEIVED
Date Well Completed _____
STATE CORPORATION COMMISSION
Plugging Commenced 10/22/84

NOV 15 1984
Plugging Completed 11/7/84

CONSERVATION DIVISION

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4218'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	216'	none
				5 1/2"	3500'	2681'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3280' & ran 6 sacks cement. Shot pipe at 2916', 2804', & 2681'. Pulled 84 joints of pipe. Plugged well with 3 hulls, 6 gel, & 115 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1984



Irene Hoover
Notary Public

My Commission expires:

15095-20457000

ROTARY DRILLERS' LOG

OPERATOR: Robert E. Campbell DRILLING COMMENCED: Jan. 20, 1976
417 S. Glendale
Wichita, Kansas 67218

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: Jan. 31, 1976
910 Union Center
Wichita, Kansas 67202

CASING RECORD: 5 Jts. 216" of used 8-5/8" cemented with 215 sacks;
114 Jts. 3500" of used 5-1/2" cemented with 125 sacks
LOCATION: Albrecht No. 1
NE NE SE
Section 18-29S-6W
Kingman County, Kansas

0 - 95 Sand
95 - 216 Red bed
216 - 290 Sand & shale
290 - 1390 Shale & sand
1390 - 1915 Shale & shells
1915 - 2196 Shale
2196 - 2605 Shale & shells
2605 - 2775 Shale
2775 - 3215 Shale & shells
3215 - 3336 Shale with lime
3336 - 3378 Lime
3378 - 3700 Shale & lime
3700 - 3820 Lime
3820 - 3895 Lime & shale
3895 - 4218 Lime

4218 Rotary Total Depth

RECEIVED
STATE COMMISSION

SEP 21 1984

REGISTRATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *J. Graves* President

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

Subscribed and sworn to before me, a Notary Public, this 4th day of February, 1976

My commission expires: February 2, 1980

Courtney M. Graves
Courtney M. Graves Notary Public

