

WELL PLUGGING RECORD

15-155-00348-0001

Give All Information Completely
Make Required Affidavit?
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Reno County, Sec. 34 Twp. 23 Rge. 9 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C NE NW

Lease Owner Sierra Petroleum Co.

Lease Name Shuff Well No. #1

Office Address Box 232, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 6-15-68 19

Application for plugging approved 19

Plugging commenced 6-20-68 19

Plugging completed 6-25-68 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3836' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3830'	3197.65'
				8 5/8"	230'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3750'. Mixed and ran 5 sacks cement thru dump bailer. Squeezed hole with 5 sacks gel, followed with 25 sacks cement, followed with 6 sacks gel, followed with 25 sacks cement, followed with 3 sacks gel and displaced with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Secy.

Box 364, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of June, 19 68

My commission expires

October 1968

Sidney D. Miller

Notary Public.

