

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 21 Twp. 23 Rge. 9 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SW

Lease Owner Mull Drilling Company

Lease Name Gowans Well No. 1

Office Address P. O. Box 349 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 7-17-70 19

Application for plugging approved 7-18-70 19

Plugging commenced 8-17-70 19

Plugging completed 8-25-70 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3720 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	210	None
				4 1/2	3720	2552'.28

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in and rigged up. Measured bottom. Released gas pressure in cellar over night. Dumped 30 gallons of sand and 4 sacks of cement on bottom. Loaded the hole. Pulled 16 1/2" tension at 1600 psi. Shot well at 3,065' and worked the pipe. Worked the pipe and shot at 2930'. Worked the pipe and gained 4 1/2". Spotted 80 bbls of oil, 47 bbls of water, 2 sacks of gel and 1 sack of hulls. Worked the pipe. Worked the pipe and gained 6" but couldn't work loose. Shot pipe at 2737' and 2510'. Worked pipe loose. Laid down 41 joints of casing. Finished laying down a total of 78 joints of casing. Loaded trailer. Cleaned out cellar. Unscrewed head. Tallied pipe. Bailed 100' of water and oil to plug. Set rock bridge at 200' and dumped 25 sacks of cement. Mudded to 40' and set a rock bridge. Capped well with 10 sacks. Loaded unit and moved off location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas


STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 3 day of September 19 70

My commission expires



Alice Hickel Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas

DONELSON DRILLING COMPANY
290 S. Pershing
Wichita, Kansas

February 8, 1967

15.155.20001-0000

Mull Drilling Company
1625 Plaza Building
Wichita, Kansas

Gowans #1

TOTAL DEPTH: 3720' R.B. Elevation: 1742 R.B. 1737 G.L.
CONTRACTOR: Donelson Drilling Co. Location: SW NE SW
COMMENCED: 1-20-67 Sec. 21-238-9W
COMPLETED: 1-29-67 Reno County, Kansas
INITIAL PROD.: Oil

Casing Record:
8 5/8 O.D. Set @ 210'
W/200 sks.
4 1/2 O.D. Set @ 3719'
W/135 sks.

FORMATION:

Surface hole
Shale and Salt
Shale
Shale and Lime
Lime and Shale
Shale and Lime
Lime and Shale
Lime W/ Shale Brks..
Lime
Shale and Sand
Lime
Mississippi Chat

DEPTH:

213
1008
1300
1885
2040
2685
2835
2915
3088
3226
3675
3720 R.T.D.

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

DONELSON DRILLING COMPANY

By: James L. Donelson
James L. Donelson

STATE OF KANSAS
COUNTY OF SEDGWICK ss.

Subscribed and sworn to me a Notary Public, this 8th day of February, 1967.

Marilyn J. Snyder
Marilyn J. Snyder

My Commission expires: May 7, 1969