

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Doonan & Sons, Inc.

ADDRESS P. O. Box 1286 Great Bend, KS 67530

PHONE (316) 792-2491 OPERATORS LICENSE NO. 7054

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3327'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	264'	none
				5 1/2	3323'	500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each side of pulled rods & tubing. Fluid to thick to run sand. Allied pumped 40 sks cement w/300# hulls followed by 13 gel, then 75 sks w/200# hulls & displaced to 550'. Shot casing at 500', spotted 35 sks cement. Pulled to 150' & circulated to surface w/60 sks. Pulled rest of casing & topped with 10 sks. Plugging complete. 60/40 poz 10% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Doonan & Sons, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of February, 19 97

Debra S. Sierberg
 Notary Public

My Commission Expires:



RECEIVED
 FEB 19 1997
 P. 07
 RECEIVED
 STATE CORPORATION COMMISSION