

LEASE NAME Schuckman-Nowak "B"

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

990 Ft. from S<sup>N</sup> Section Line

1650 Ft. from E<sup>W</sup> Section Line

SEC. 18 TWP. 13 RGE. 15 ~~XX~~ (W)

COUNTY Russell

Date Well Completed 8-8-84

Plugging Commenced 6-6-97

Plugging Completed 6-9-97

LEASE OPERATOR Quality Well Service, Inc.

ADDRESS 249 E. Beth Drive Sterling, Ks. 67579

PHONE (316) 727-3410 OPERATORS LICENSE NO. 31925

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-16-97 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top \_\_\_\_\_ Bottom 3297' T.D. 3379'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	713'	
				5 1/2"	3377'	2227'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Sanded to 3017'. Bailed 4 sks cement. Shot at 2711' & 2517'. Shot at 2400' & 2227'. Pulled to 1600'. Pumped 110 sks/5 hulls. Pulled to 1000'. Pumped 40 sks/2 hulls. Pulled to 500'. Pumped 30 sks. Pulled to 150'. Circulated cement to surface. Pulled rest of pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 E. Beth Drive Sterling, Ks. 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Quality Well Service, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Sharon McIntyre (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein stated and the log of the above-described well as filed the the same are true and correct.

RECEIVED  
KANSAS CORPORATION COMMISSION  
RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 16 1997

(Signature) Sharon McIntyre

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 12th day of June, 19 97

CONSERVATION DIVISION  
WICHITA, KS  
CONSERVATION DIVISION  
WICHITA, KS

Cheryl L. Mishler  
Notary Public

My Commission Expires: 6/3/99

USE ONLY ONE SIDE OF EACH FORM

CHERYL L. MISHLER  
State of Kansas  
My Appt. Exp. June 3, 1999