

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-20,888-0070

LEASE NAME Eulert 'B'

WELL NUMBER 6

 Ft. from S Section Line

 Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

SEC. 4 TWP. 12 RGE. 15 (W)

ADDRESS Shields Building - Russell, Ks. 67665

COUNTY Trussell

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed

Character of Well Oil

Plugging Commenced 3-14-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-15-96

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom 2450'

Show depth and thickness of all water, oil and gas formations.

3-26-96

RECEIVED
KANSAS CORP. DIV.
MAR 26 1996

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	535'	none
				4 1/2"	2449'	1822'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Plugged off bottom with sand to 2300', dumped 4 sacks cement. Shot pipe at 2018', and 1822', pulled to 1400' pumped 65 sacks cement, 300# hulls; pulled casing up to 775' pumped 40 sacks cement, 200# hulls. Pulled to 275' pumped 95 sacks cement, circulated to surface, (60/40 POZMIX 10% ael) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc. -Russell, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed t
the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 96.

Irene Herzberg
Notary Public

My Commission Expires:

