

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155 - 26475-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name National Oil Company

Complete Address Suite 200, 1350-17th Street, Denver, Colorado. 80202

Lease Name Lundstrom Well No. 1

Location C SW NW Sec. 21 Twp. 23 Rge. 9 (~~EAST~~)(West)

County Reno Total Depth 3697'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling and Sun Oilwell Cementing, Inc.

Address Box 176, Chase, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 10:30 AM Day: 14 Month: December Year: 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows: 8 5/8" - 287' - 225 sacks 4 1/2" - 3697' - 100 sacks  
PBTD - 3694 Perf 3667-86

Hole making gas. 4 1/2" casing squeezed w/ 35 sacks common cement - plug pumped  
to 3000' under 1200 PSI. Hole squeezed with 15 sacks gel, 4 sacks  
hulls, 10 sacks gel, 8 5/8" plug, and 100 sacks 50-50 Permex with 2% gel  
pumped into 8 5/8" surface casing. Closed in at 150 P.S.I.

2905' of 4 1/2" casing recovered.

RECEIVED  
STATE CORPORATION COMMISSION  
12-16-81  
DEC 16 1981

CONSERVATION DIVISION  
Wichita Kansas

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

DATE 1-7-82  
INV. NO. 8837-W