

13.063.30406.00.00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1967

6-12-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company.

Complete Address: 705 4th National Bank Building, Wichita, Kansas.

Lease Name Owens Well No. A-1

Location CNE-SW Sec. 21 Twp. 15 Rge. (E) (W) 27

County Gove Total Depth 4390

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 10:45AM Day 8 Month 6 Year 1967

The Above well was plugged as follows:

223'--8 5/8" Surface pipe, cement circulated with 155 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 240', set plug and displaced 20 Sx. cement

thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement

to bottom of cellar.

(Cementing operations performed by Globe Oil Well Cementing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 6/13/67

INV. NO. 5375-W