

15.063.00-23.00.01  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name California Time Petroleum Company,  
Complete Address 9460 Wilshire Blvd., Beverly Hills, California.  
Lease Name Jacka Well No. 1  
Location CSE-SE Sec. 8 Twp. 15 Rge. (E) (W) 26  
County Gove Total Depth RTD-4300' Probable Drill-out 4178'  
Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated   
Plugging Contractor Knight Casing Pulling Company, Incorporated,  
Address Box #405 License No. 436  
Operation Completed: Hour 11:30 AM Day 9 Month 1 Year 1971

The above well was plugged as follows:

172'--8 5/8" Surface casing, cement circulated.

4175'--4 1/2" Production casing cemented on bottom with 150 Sx. No plug back nor per-  
forations indicated.

Squeezed 4 1/2" casing initially with 20 Sx. cement and followed with 22 Sacks gel from  
3975' to 675' then 55 Sx. cement from 675' to bottom of cellar. Maximum Pump-in press-  
ure-400#. Final shut-in pressure-200#. Squeezed anulus initially with 5 sacks hulls  
and 15 sacks gel and finally with 135 Sx. cement from 675' to bottom of cellar.

Maximum pump-in pressure-1000#. FSIP-500#. (Mudding and Cementing operations per-  
formed by Globe Cementing, Inc.,).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Nichols  
Well Plugging Supervisor

DATE 1-12-71

INV. NO. 3185-W