

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
15.063.20150.00.00
CONSERVATION DIVISION AGENT'S REPORT
RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company,
Complete Address 705 Fourth National Bank Building, Wichita, Kansas.
Lease Name Jilg Well No. A-1
Location 150' NW of CNW-NE Sec. 1 Twp. 14 Rge. (E) (W) 30
County Gove Total Depth 4390'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 7:30 PM Day 27 Month 11 Year 1972

The above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displace 110 Cu. Ft. cement
thru DP from 1075' to 750'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/1/72
INV. NO. 6683-W