


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Finney County. Sec. 17 Twp. 24S Rge. 31 ~~XX~~/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SW/4



Locate well correctly on above Section Plat

Lease Owner Anadarko Production Company  
Lease Name MORRIS "D" Well No. 1  
Office Address P. O. Box 351, Liberal, Kansas 67901  
Character of Well (Completed as Oil, Gas or Dry Hole) Gas  
Date Well completed 2-9 1957  
Application for plugging filed 9-26 1978  
\* Application for plugging approved 10-13 1978  
Plugging commenced 2-8 1979  
Plugging completed 2-8 1979  
Reason for abandonment of well or producing formation replacement well drilled

If a producing well is abandoned, date of last production  
Unknown (well was abandoned when purchased by APC) 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.  
Producing formation Hugoton (Kridler) Depth to top 2605 Bottom 2642 Total Depth of Well 2646'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kridler	Gas	2605	2642	5-1/2"	2644	0
Glorietta	Water	1452	1683	8-5/8"	540'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Spot 20 sxs cmt 2628-2508, drlg mud 2508-666', spot 20 sxs cmt 666'-546', drilling mud 546-91, spot 10 sxs cmt 91'-surface.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1979 2-27-1979

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF KANSAS COUNTY OF SEWARD, ss.  
Paul Campbell (employee of owner) or ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell  
P. O. Box 351, Liberal, Kansas 67901 (Address)

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of February, 1979

STATE NOTARY PUBLIC  
BEVERLY J. WILLIAMS  
Seward County, Kansas  
My Appt. Exp. 11/21/82

Beverly J. Williams  
Notary Public.

My commission expires November 21, 1982

\*Renewed plugging authority by State Corporation Commission on January 22, 1979.