

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,121-0000

LEASE NAME Morris

WELL NUMBER 1

1320' Ft. from S Section Line

1320' Ft. from E Section Line

SEC. 19 TWP. 24s RGE. 31w (E) or (W)

COUNTY Finney

Date Well Completed 1-30-74

Plugging Commenced 4-9-03

Plugging Completed 4-9-03

RECEIVED
APR 11 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Warrior Inc

ADDRESS P.O.Box 399, Garden City, Ks 67846

PHONE (620-275-2963) OPERATORS LICENSE NO. 4058

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-8-03 (date)

by Steve Middleton District One (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Krider Depth to Top 2628' Bottom 2638' T.D. CIBP@ 2590'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	379	0	8-5/8"	379'	None
	Production	2710'	0	4 1/2"	2710'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each section.

Set CIBP @ 2590' Dump 2 sks cement on top, ran bond log, top cem. in Ann. 152'
Perf 1406' press to 2500#s, perf. 1485' T.R. 2 BPM 1500#s
Mix & pump 100 6-/40 p0z. 6% gel & 2 sks hulls down 4 1/2" csg. SI w/ 750#s.
Hook up to Ann. pump 25 sks cem, Si. @ 500#s. job complete 12:30 PM. 4-9-03.

Name of Plugging Contractor Swift Services Inc License No. 32382

Address P.O.Box 466, Ness City, Ks. 67560


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior Inc

STATE OF Kansas COUNTY OF Finney, ss.

Kevin Wiles Sr ? Production Supt. (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact:
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) _____



SWORN TO before me this 9th day of April 192003

Debra J. Purcell
Notary Public

My Commission Expires: 11/4/03