


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 35 Twp. 24S Rge. (E) 24W (W)  
Location as "NE/CNW%SW%" or footage from lines NE NE NE  
Lease Owner T. L. Ferrier  
Lease Name No. 1 Fischer Well No. 1  
Office Address 200 W. Douglas, Suite 250, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-29 19 73  
Application for plugging filed 8-29 19 73  
Application for plugging approved 8-29 19 73  
Plugging commenced 8-29 19 73  
Plugging completed 8-29 19 73  
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4905 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Fluid	Surface	401	8-5/8"	393	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fluid to 660', plug, 70 sx cement;  
Fluid to 420', plug, 20 sx cement;  
Fluid to 40', plug, 1/2 sx hulls, 10 sx cement;

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1973  
CONSERVATION DIVISION  
Wichita, Kansas

9-10-1973

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor D N B DRILLING, INC.  
Address 701 First Nat'l Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF \_\_\_\_\_, SS.  
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
701 First Nat'l Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 73

My commission expires August 25, 1976

Ella Priess  
Notary Public.

Ella Priess  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

T. L. FERRIER  
No. 1 Fischer  
NE NE NE, Sec. 35-24S-24W  
Hodgeman County, Kansas

Elevation: 2472 K.B.

Commenced: 8-22-73  
Completed: 8-29-73

Surface Casing: 393' of 8-5/8"  
cemented w/225 sx common cement,  
3% cc. 8-22-73

FORMATION

DEPTH

Surface Hole	0 - 401
Shale	401 - 565
Shale & Sand	565 - 1063
Blaine Anhydrite	1063 - 1074
Sand & Red Bed	1074 - 1607
Stone Corral Anhydrite	1607 - 1631
Shale	1631 - 2195
Shale & Lime	2195 - 2580
Lime & Shale	2580 - 4170
Lime	4170 - 4750
Lime & Chert	4750 - 4827
Lime	4827 - 4905 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D. N. B. DRILLING, INC.


*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 5th day of September, 1973.

My Commission Expires:  
August 25, 1976

*Ella Priess*  
Ella Priess, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1973  
CONSERVATION DIVISION  
Wichita, Kansas