

To: 051538
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-19
API NUMBER 15-083-21,379-0000 145
NE SE NW, SEC. 2, T. 24 S, R. 24 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6710

Operator: McNeish Oil Operations

Name & Address P.O. Box 734

Winfield, KS 67156

3630 feet from S section line

2970 feet from E section line

Schraeder/Coltrain

Lease Name Well # 1

County Hodgeman 157.52

Well Total Depth 4847 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 19 Month: 3 Year: 19 92

Plugging proposal received from Jay Snider

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1616-40'

1st plug at 1640' with 50 sx cement, 2nd plug at 800' with 80 sx cement,

3rd plug at 310' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12 p.m. Day: 19 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1640' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 310' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or others) observe this plugging.

DATE 4-7-92

INV. NO. 34885

Signed Richard M. Lacey
(TECHNICIAN)