

To: 1 090058
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-7
API NUMBER 19-083-21,327-0600

App: SW SE SW, SEC. 15, T 24 S, R 25 W/E
330 feet from S section line
3580 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9534 Lease Name Hugo Foster Well # 1
Operator: Giant Exploration & Production Corp County Hodgeman 209.13
Name & Address P.O. Box 2810
Farmington, NM 87499
Well Total Depth 6435 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 407.53

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:15 p.m. Day: 6 Month: 3 Year: 19 91
Plugging proposal received from Doug

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4674' w/135 sx cement, PBTD 4719', Perfs at 4506-4620' (4 sets)
1st plug pump 2 sx hulls and 25 sx cement down 2 3/8" tubing,
2nd plug at 1690' with 50 sx cement, 3rd plug at 800' with 80 sx cement,
4th plug at 440' with 50 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 9:20 a.m. Day: 7 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 1/2 sx hulls and 25 sx cement down 2 3/8" tubing,
2nd plug pulled to 1690', pumped 50 sx cement, displaced 35 bbls. mud, circulated.
Tried to pull, pipe was hung up.
3rd plug shot casing at 819', spotted 80 sx cement,
4th plug pulled to 440', spotted 50 sx cement,
5th plug pulled to 40', pumped 10 sx cement. Had circulation.

Remarks: Used 60/40 Pozmix. 6% gel by Sargent's. Recovered 819' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

~~do not~~ observe this plugging.

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
3-11-91
MAR 11 1991

INVOICED
DATE 3-15-91
INV. NO. 31174
3-7