

1 030813

6-2-87

API NUMBER 15-069-20,205-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE, SEC. 21, T 24 S, R 30 W W

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Irsik Well # 1-21

Operator: Rine Exploration Company

County Gray 162.50

Name & Address 300 West Douglas, Suite 645

Well Total Depth 5000 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 538

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rine Drilling Company License Number 5654

Address 300 West Douglas, Suite 600, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 2 Month: 6 Year: 1987

Plugging proposal received from Don Noreuil

(company name) Rine Drilling Company (phone) 316-267-1333

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1770-1940'

1st plug at 1950' with 50 sx cement, 2nd plug at 900' with 50 sx cement,

3rd plug at 570' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

 Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12 p.m. Day: 2 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1950' with 50 sx cement,

2nd plug at 900' with 50 sx cement,

3rd plug at 570' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED (if applicable) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 6-9-87

INV. NO. 17204
6-2