

1 050837

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21,257-0000

NE NE SE, SEC. 4, T 24 S, R 24 W/E

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line

330 feet from E section line

Operator License # 4704

Lease Name Sinclair Well # 43-4

Operator: True Oil Company

County Hodgeman 157.63

Name & Address P.O. Box 2360

Well Total Depth 4850 feet

Casper, Wyoming 82602

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 858

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor True Drilling Company License Number 4708

Address P.O. Drawer 2360, Casper, WY 82602

Company to plug at: Hour: 6:00 am Day: 26 Month: July Year: 19 86

Plugging proposal received from Buzz Montgomery

(company name) True Drlg. (phone) (307) 266-0230

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2485'
Anhydrite 1646'

1st plug at base of Anhydrite with 50 sx of cement

2nd plug at 875' with 50 sx cement

3rd plug at 40' to surface with 10 sx cement

4th plug to circulate the rat hole with 15 sx cement

5th plug to circulate the mouse hole with 10 sx cement

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 am Day: 26 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1646' with 50 sx cement, 2nd plug at 888' with 50
sx cement, 3rd plug from 45' to surface with 10 sx cement, 4th plug to circulate

rat hole with 15 sx cement and 5th plug to circulate mouse hole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
600 S. LIV. WICHITA, KS

7-31-86

JUL 31 1986

Remarks: Used 60/40 Pozmix with 6% gel pumped by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (If not, observe this plugging.)

DATE JUL 31 1986

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 14591