

API Well Number: 15-001-22508-00-00

Kansas Corporation Commission

District Plugging Report

Spot: NWNENW Sec 31 Twp 26 S Rng 19 ☒ E / ☐ W4650 Feet from ☐ N / ☒ S Line of Section3200 Feet from ☒ E / ☐ W Line of SectionGPS: Lat: 37.745619 Long: 95.372289 Date: 11/30/15 7/28/14Lease Name: Townsend Well #: TOW 11County: Allen Total Vertical Depth: 725 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>State of Kansas</u>	<u>DRIVE - Drive Pipe</u>	<u>14.000</u>	<u>8</u>	<u>0</u>	
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>HOLE - Hole 1</u>	<u>8.000</u>	<u>10</u>	<u>10</u>	
Address 2: _____	<u>TI - Tubing 1</u>	<u>2.000</u>	<u>750</u>	<u>0</u>	
City: <u>Wichita</u>					
State: <u>Ks</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 11/9/15 / _____Plug Co License No.: 6372 Plug Co. Name: Splane Pulling and Roustabout Services, Inc.Proposal Revd from: Kerth Splane Company Name: Same Phone: (620) 431-1359Proposed
Plugging
Report:

Clean out wells to TD. Pump full of cement inside and outside of tubing. Perforate if not completed Alternate II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%Date/Time Plugging Completed: 11/9/15 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report: _____ Perfs: _____ Top _____ Bottom _____ Thru _____


Clear location. Drill inside of 2" to 750 ft. Drill out the iron oxide build-up so 1" pipe could be run to plug depth. Pull drill pipe out and run 1" to 750 ft inside 2" and to 500 ft outside of 2". Pump Portland cement to surface inside and outside 2". Pull pipe and top off well. Pump total of 289 sacks of cement. Well plugged.

Remarks: Contract No. 40432. Control No. 20150019-011. GPS'ed by TA and FG NAD 83. Reg. SectionPlugged Thru: TBG - TubingPlugged Due to Compliance Issue: ☐ Yes ☒ NoDistrict: 03

KCC WICHITA

DEC 07 2015

RECEIVED



(Technician)

Form: District Plugging Report - _____