

API Well Number: 15-001-22507-00-00
 Spot: NWSWNW Sec 31 Twp 26 S Rng 19 E / W
3800 Feet from N / S Line of Section
4586 Feet from E / W Line of Section
 GPS: Lat: 37.743340 Long: 95.377110 Date: 3/24/16 11/10/15
 Lease Name: Townsend Well #: TOW 16
 County: Allen Total Vertical Depth: 820 feet

Kansas Corporation Commission
District Plugging Report

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>State of Kansas</u>	<u>DRIVE - Drive Pipe</u>	<u>12.000</u>	<u>8</u>	<u>0</u>	
Address 1: <u>266 N. Main St. Ste. 266</u>	<u>HOL1 - Hole 1</u>	<u>8.000</u>	<u>10</u>	<u>10</u>	
Address 2: _____	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>820</u>	<u>0</u>	
City: <u>Wichita</u>	<u>T2 - Tubing 2</u>	<u>1.000</u>	<u>800</u>	<u>800</u>	<u>Packer</u>
State: <u>Ks</u> Zip Code: <u>67202</u> - <u>1513</u>					

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 3/15/16 / _____
 Plug Co License No.: 6372 Plug Co. Name: Splane Pulling and Roustabout Services, Inc.
 Proposal Rcvd from: Keith Splane Company Name: Same Phone: (620) 431-1359

Proposed Plugging Report: Clean out wells to TD. Pump full of cement inside and outside of tubing. Perforate if not completed Alternate II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: PART - Partial
 Date/Time Plugging Completed: 3/15/16 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Clear location. Pull on 1". Had trouble getting packer loose. Pull 800 ft of 1" and packer out of 2" pipe. Run 1" inside 2" to 800 ft. Run 1" outside 2" to 500 ft. Pump Portland cement to surface inside and outside 2". Pull pipe and top off well. Pump total of 279 sacks of cement. Well plugged.				

Remarks: Contract No. 40423. Control No. 20150019-016. GPS'ed by TA and FG NAD 83. Irreg. Section

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 KCC WICHITA Frank Guilfoyle
 (Technician)

APR 05 2016 RECEIVED Form: District Plugging Report - _____