

1080149

10-8

15-055-10165-0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Spud date 4/13/63

C SW, SEC. 33, T 24 S, R 31 (W) E  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31458

Lease Name Garden City A Well # I

Operator: H J Inc. d.b.a. Herman Lang Oil & Gas  
Name & Address 70 N. Farmland Rd.  
Garden City, KS 67846

County Finney 86.74

Well Total Depth 2669 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 550

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mikes Testing & Salvage Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 9 a.m. Day: 8 Month: 10 Year: 19 97

Plugging proposal received from Kenneth Lang

(company name) H J Inc. (phone) 316-275-0311

work: 5 1/2" at 2650' w/200 sx cement, Perfs at 2627-48, Open hole 2650-2669

Tubing fish sanded in at 1770', casing leak approx. @ 1700'

1st plug run tubing and 5 1/2" AD-1 packer to 1150', pump 80 sx cement with 100 lbs. hulls pumped in last 25 sx cement, displace to 1500'.

2nd plug pull packer and tubing, shoot casing at 530' and pump 125 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 8 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing and 5 1/2" AD-1 packer to 1150' and pumped 80 sx cement with 100 lbs. hulls pumped in the last 25 sx cement. Displaced to 1500'.

Maximum pressure 500 psi and shut in 400 psi.

Pulled packer and tubing.

2nd plug shot casing at 530' and pumped 125 sx cement, circulating cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

INVOICED

(Additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE OCT 23 1997

Signed Kevin D Strube (TECHNICIAN)

INV. NO. 49268

RECEIVED STATE CORPORATION COMMISSION 10-16-97 OCT 16 1997

CONSERVATION DIVISION SURFACE Kansas