

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Elmo Morgenstern of Clarke Corporation has this

date requested permission to plug the following described well:

Operator's Full Name: McCoy Petroleum Corporation

Complete Address: One Main Place, St. 410, Wichita, Kansas 67202

Lease Name: Mathes Well No. 1

Location: SE NE NW Sec. 29 Twp. 30 Rge. 7W (E) (W)

County: Kingman Total Depth: 4271'

Abandoned Oil Well XX Gas Well Input Well SWD Well D&A

Other well as hereafter indicated:

Mr. Elmo Morgenstern was instructed to plug the well as follows:

242' of 8 5/8" SP

4 1/2" set @ 4271' W/100 sks

Top Perf 4253' Sand back to 4235' W/4 sks

Pump 15 gel 8 hulls 10 gel, Release plug and displace W/125 sks of

50/50 pozmix 4% gel 3% C.C. SIP 800# Recovered 3604'-4 1/2' csg.

Cemented by Allied

Very truly yours,

M. V. Leslie
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981
CONSERVATION DIVISION
Wichita, Kansas
10-13-81