

State of Kansas



15-095-20026-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1967

6-16-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed June 1, 1967.

Dear Sir:

Mr. Norman Rodie of Rains & Williamson Oil has this

date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Co. & Rains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Holland Well No. # 1

Location: C NE SE Sec 26 Twp. 30 Rge. 7 (E)(W) W

County Kingman Total Depth 4709' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rodie was instructed to plug the well as follows:

224' of 8 5/8" surface pipe, cement circulated with 165 sacks. Fill hole with drilling mud to 220', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent