

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1972 2-22-72
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Berens of D.N.B. Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.

Operator's full Name: Thornton E. Anderson

Complete Address: 710 Union Natl Bldg. Wichita, Ks

Lease Name: Lechner Well No. 2

Location: A/ NE/SE Sec. 25 Twp. 30s Rge. 7 (E)(W) W

County: Kingman Total Depth 4692 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Berens was instructed to plug the well as follows:

240 ft 8 5/8 surface pipe cemented with 250 sacks. Fill
hole to 220 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud
to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent