

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 20 1967

10-20-67
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed October 18, 1967.

Dear Sir:

Mr. Rod Sweetman of Sweetman Drilling, Inc. has this
 date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company

Complete Address: 700 One Twenty Bldg., Wichita, Kansas 67202

Lease Name: Hunter Well No. # 1

Location: SE NE Sec. 32 Twp. 30 Rge. 7 (E)(W) W

County Kingman Total Depth 3368' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill
hole with drilling mud to 200', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent