



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Jack Sullivan of Sierra Petroleum Co., Inc has this
date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Sierra Petro. Co. & Amerada Petro. Corp.

Complete Address: 1015 Wichita Plaza, Wichita, Kansas

Lease Name: Creighton Well No. # 1

Location: C NW SW Sec. 33 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4788 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

205' of 8 5/8" surface pipe, cemented with 190 sacks. Fill
hole with drilling mud to 200', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent