

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

R
 VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 17 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Mason of Dunne-Gardner Drilling Co. Inc. this

date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Dunne - Gardner Drilling Co. Inc.

Complete Address: 300 Schweiter Bldg. Wichita, Kansas

Lease Name: Benish Well No. # 1

Location: C W/2 NW/4 NE/4 Sec. 9 Twp. 24 Rge. 24 (E)(W)

County Hodgeman Total Depth 4800' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

8 5/8" - 252' Circulated w/cement.

Mud 4800' to 500' Hulls, 20 Sax. cement. 500' to 440'

Mud 440' to 250' Hulls, 25 Sax. cement 250' to 175'

Mud 175' to 40' Hulls, 10 Sax. cement 40' to surface.

Very truly yours,

Hugh Scott
 Conservation Division Agent