



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Abercrombee of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Abercrombee guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co. Inc.

Complete Address: 220 W. Douglas, Wichita, Kansas

Lease Name: Benish Well No. 1

Location: NE SW NW Sec. 9 Twp. 24 Rge. 24 ~~(E)~~ ^{XX} (W)

County: Hodgeman Total Depth 4825' ~~off Well~~

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Abercrombee was instructed to plug the well as follows:

8 5/8" to 295' circulated w/ cement. Mud 4825' to 600'

Spot 70 sacks cement 600' to 380' Mud 380' to 270'

Spot 20 sacks cement 270' to 200' Mud 200' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent