

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 36-28

LOCATION 1/2 - NW - SW

SEC. 11 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 8 Lease Fuller, A.

Operator Stanford Oil & Gas Co. Address Box #7 - Ellinwood - Kans.

Field _____ County Stafford

Total Depth 3803 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 245 ft. Circulated with cement.
5% casing at 3739 ft. Cemented with 100 sacks cement
Plugged back to 3730 ft with chat. Pumped 5 sacks of
cement at 3730 ft. Shot off & Pulled the 5% casing -
Filled hole with mud to 245 ft. Set Rock Bridge &
15 sacks cement at 245 ft. Used to 30 ft. Plug &
10 sacks of cement at the surface.
Pipe Pulling, Inc. Plugging Contractors.

RECEIVED
NOV 24 1950 11-24-50
DISTRICT CONSERVATION COMMISSION

E. D. Stough
District Conservation Agent

Date 11-30-50

PLUGGING
FILE SEC 11 T 24 R 11W
BOOK PAGE 36 LINE 88