

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 130-28

LOCATION CW/2-SW/4-SW/4

SEC. 11 TWP. 24 RGE. 11

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 9 Lease A. Fuller

Operator Standard Oil Co Address Box #7, Ellinwood, Kans

Field _____ County Stafford

Total Depth 3822 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 255 ft. Circulated with cement.
7" casing set at 3749 ft. Plugged back from bottom
to 3740 ft with chat - Dumped 6 sacks of cement in the
7" casing at 3740 ft - Shot off & Pulled the 7" casing.
Filled with mud to 255 ft - Rock Bridge & 28 sacks of
Cement at 255 ft - Mud to 30 ft - Bridge & 10 sacks of
Cement at the surface.

General Tool Co - Plugging Contractors

RECEIVED

E. M. Stough
District Conservation Agent

Date 1-14-50

PLUGGING
FILE SEC 11 T 24 R 11
BOOK PAGE 139 LINE 28

KANSAS 1-16-50