

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 55-22

LOCATION QW/2 - NW - NW

SEC. 11 TWP. 24 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease R. Karbsom

Operator Stanford Oil & Gas Co Address Box #518 - Leuth - Kansas

Field _____ County Stafford

Total Depth 3767 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 249 ft. Circulated with cement.
5 1/2 casing set at 3763 - Filled back down bottom
to 3700 ft. with chert & sand - Dumped 5 sacks of cement
at 3760 ft - Shot off & Pooled 5 1/2 casing - Filled with
mud to 245 ft - Bridge & 20 sacks of cement at 245 ft -
mud to 20 ft below the surface - Plug & 10 sacks of
cement - Hargett & Lynch - Pitt Pulling - Contractor

PLUGGING
FILE SEC. 11 TWP. NW
BOOK PAGE 55 LINE 22

C. D. Stough
District Conservation Agent
Date 9 - 27 - 48 9-27-48