

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 34-12LOCATION S $\frac{1}{2}$ -SE-SESEC. 11 TWP. 24 RGE. 11WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 7 Lease C. HayesOperator Standard Oil & Gas Co. Address Box #7 - Ellinwood - Kans.Field _____ County StaffordTotal Depth 3809 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 $\frac{3}{4}$ - 251 $\frac{1}{2}$ - Circulated with cement.
7" casing set at 3750 $\frac{1}{2}$ - Plugged back to 3771 $\frac{1}{2}$ with cement.
from 3771 $\frac{1}{2}$ to 3740 $\frac{1}{2}$ with chat - Dumped 6 sacks of
cement at 3740 $\frac{1}{2}$ - Shot off & pulled the 7" casing - mud
to 251 $\frac{1}{2}$, Set Rock Bridge & 10 sacks of cement at 251 $\frac{1}{2}$
mud to 30 $\frac{1}{2}$ - Bridge & 10 sacks of cement
at the surface
Pipe Pulling, Inc. Plugging Contractors

RECEIVED

Conservation Div.
5-31-50
MAY 31 1950

C. H. STOUGH

District Conservation Agent

Date 5-27-50

