

KANSAS

Form CP-3
Rev. 6-26-62STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
OCT 24 1967
10-20-67
CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202Intent to Drill,
filed October 18, 1967.Operator's Full Name Beardmore Drilling CompanyComplete Address: 700 One Twenty Bldg., Wichita, Kansas 67202Lease Name Hunter Well No. # 1Location SE NE Sec. 32 Twp. 30 Rge. 7 (E) (W) WCounty Kingman Total Depth 3368'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sweetman Drilling, Inc.Address: Box 645, Great Bend, Kansas 67530 License No. _____Operation Completed: Hour 1:00PM Day 27th Month October Year 1967

The Above well was plugged as follows:

205' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was
filled with drilling mud to 200', 1st cementing plug, bridged with 2 sacks
of dry cement and 1/2 sack of hulls on fluid at 200', and cemented with 23
sacks, with cement from 190' to 115'. Hole was filled with drilling mud to
40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of
hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to
the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 10/30/67INV. NO. 6575-W