

*ep*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE  
2-21-66  
FEB 21 1966

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name Hostettler Well No. # 1

Location NE NW Sec. 32 Twp. 30 Rge. 7 (E) (W)W

County Kingman Total Depth 4769'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:30PM Day 16th Month Feb. Year 1966

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated/ 4769' of 4 1/2" long string,  
cemented with 75 sacks. Plug back to 4757'. Top perferation 4752'. Bottom  
of the hole was sanded to 4740', and cemented with 3 sacks, through the  
dump bailer. 4300' of 4 1/2" long string was recovered from the hole. Hole  
was filled with mud to 250', rock bridge from 250' to 240', and cemented  
with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to  
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 2/21/66  
INV. NO. 2754-W

Signed: Archie Elving  
Well Plugging Supervisor