

15-095-30082-0000

Form CP-3
Rev. 6-26-62

KANSAS

W STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-1-66
JUN -1 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name McClure Oil Company

Complete Address: 1301 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Wells Well No. # 1

Location SW NE Sec. 33 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4745'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30PM Day 31st Month May Year 1966

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated. 4743' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was
sanded to 4725', and cemented with 5 sacks, through the dump bailer.
3200' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was at 280', rock bridge from 280' to 270'. 5 sacks of cement was put on
the plug at 270', and let set over-night. Next day hole was filled with
4 yards of ready-mix cement from 255' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 6/1/66
INV. NO. 3316-4